MindScape: AI-Based Mental Wellness and Stress Relief System Using Natural Language Processing and Voice Assistance

THIRD YEAR

MINI PROJECT REPORT

Submitted by

RAKSHANAPOOJA.B -24623123

SALMA.S - 24623125

in partial fulfilment for the award of the degree of

BACHELOR OF TECHNOLOGY IN CSE

ARTIFICIAL INTELLIGENCE

DEPARTMENT OF ARTIFICIAL INTELLIGENCE AND MACHINE LEARNING
SCHOOL OF ENGINEERING
VELS INSTITUTE OF SCIENCE, TECHNOLOGY AND ADVANCED STUDIES (VISTAS)
CHENNAI - 600 117
NOVEMBER 2026

BONAFIDE CERTIFICATE

Certified that this project report "**MINDSCAPE: AI-BASED MENTAL WELLNESS AND STRESS RELIEF SYSTEM USING NATURAL LANGUAGE PROCESSING AND VOICE ASSISTANCE"** is the bonafide work of **RAKSHANAPOOJA B – 24623123** and **SALMA S – 24623125,** who carried out the project under my supervision. Certified further that, to the best of my knowledge, the work reported here does not form part of any other project report or dissertation on the basis of which a degree or award was conferred on an earlier occasion on this or any other candidate.

SIGNATURE OF THE HOD
Dr. K. Ulaga Priya M.E., Ph.D
Associate Professor & Head
Department of AI&ML
School of Engineering
VISTAS, Chennai

SIGNATURE OF THE SUPERVISOR
Dr. Usha
Department of AI&ML
School of Engineering
VISTAS, Chennai

Submitted for the Project Work and Viva-Voce examination held on..... at Vels Institute of Science, Technology and Advanced Studies (VISTAS), Chennai – 600 117.

INTERNAL EXAMINER **EXTERNAL EXAMINER**

DECLARATION

We hereby declare that the mini project report entitled "**MINDSCAPE: AI-BASED MENTAL WELLNESS AND STRESS RELIEF SYSTEM USING NATURAL LANGUAGE PROCESSING AND VOICE ASSISTANCE**", submitted to Vels Institute of Science, Technology and Advanced Studies (VISTAS), Chennai, in partial fulfillment of the requirements for the award of the degree of Bachelor of Technology in Computer Science and Engineering (Artificial Intelligence), is a record of original work carried out by us under the guidance of **Dr.Usha R** , Assistant Professor, Department of Artificial Intelligence and Machine Learning. The work has not been submitted, in part or in full, for the award of any other degree or diploma.

Place: Chennai **RAKSHANA POOJA. B -24623123**

Date: 30.10.2026 **SALMA.S - 24623125**

ACKNOWLEDGEMENT

It is a great delight and a proud privilege to acknowledge the help and support we received from the positive minds around us in making this venture a success. The infrastructural support and lab facilities provided by the institution have been a motivating factor in the completion of this project work, and we thank the **Founder & Chairman, Shri. Dr. Ishari K. Ganesh**, with great pleasure.We are grateful to our **Head of the Department, Dr. K. Ulaga Priya**, for her continuous support, from the early stages of conceptual inception through to the completion of this work. We extend our warmest thanks to our **Internal Guide, Dr. Usha,** who patiently guided us and provided invaluable advice and encouragement throughout the project.We also thank the staff members, the Librarian, and the non-teaching staff of the Computer Centre, who supported us throughout. Last but not least, we thank our parents and friends for their constant support and encouragement, without which this project would not have been possible.

RAKSHANAPOOJA B – 24623123

SALMA S – 24623125

CHAPTER NO.	TABLE OF CONTENT	PAGE NO.
	ABSTRACT	iv
	LIST OF FIGURES	v
	ABBREVIATIONS	vi
1	**INTRODUCTION**	**1**
	1.1 Overview of the project	1
	1.2 Scope and objective	2
2	**LITERATURE REVIEW**	**5**
	2.1 Literature Overview	5
	2.2 Literature Survey	5
3	**SYSTEM DESIGN**	**7**
	3.1 Existing System	7
	3.2 Proposed System	7
	3.3 System Architecture	7
	3.4 Hardware Requirements	8
	3.5 Software Requirements	8
4	**IMPLEMENTATION**	**10**
	4.1 Methodology	10
	4.2 Implementation	10
	4.2.1 Journal and Mood Module	10
	4.2.2 Self-Understanding Module	10
	4.2.3 Productivity Module	10
	4.2.4 Gratitude and Grounding Module	11
	4.2.5 Analytics and Achievements Module	11
	4.2.6 Risk Screening and AI Reflection Module	11
	4.2.7 Voice and Multilingual Module	12
	4.2.8 Data Management Module	12
	4.3 Safety and Ethical Design	12
5	**CONCLUSION AND FUTURE WORK**	**13**
	5.1 Conclusion	13
	5.2 Future Work	13
	5.3 Source Code	14
	5.4 Results	55
	REFERENCES	**59**

ABSTRACT

MindScape is a privacy-first, web-based personal wellness and self-reflection platform that unifies dream and scenario journaling, mood tracking, structured self-understanding tools, productivity aids, guided healing exercises, and AI-assisted reflective storytelling grounded in secular and user-selected wisdom traditions. Unlike conventional mood-tracking or journaling applications, MindScape is built around three deliberate design constraints: first, it never attempts to clinically diagnose or assess the user; all reflective scoring is transparent and self-reported; second, all personal data remains under the user's direct control through browser-local storage with explicit export and import; and third, any AI-generated content is screened against crisis-indicating language before generation and is presented as a clearly separate, optional reflection rather than being merged into the user's authentic journal.The current prototype is implemented entirely as a client-side single-page application using HTML5, CSS3, and vanilla JavaScript (ES6+), integrating a generative AI language model API for reflective content and native browser Web APIs: the Web Speech API for voice journaling and the SpeechSynthesis API for multilingual audio playback of wisdom content. No backend server or database is used in the current build; all data persists locally in the user's browser via the localStorage API.This report documents MindScape's system design, technology stack, module-wise architecture, implementation highlights, safety and ethical design considerations, testing strategy, and the roadmap required to evolve the prototype into a production-grade, multi-user application backed by a real server, database, and authentication system.

Keywords: digital well-being, AI-assisted journaling, mood tracking, risk-screened AI reflection, voice assistance, privacy-first design, localStorage.

LIST OF FIGURES

FIGURE NO.	TITLE	PAGE NO.
Figure 1	MindScape data-flow architecture	7
Figure 2	Risk-screened AI reflection pipeline	11
Figure 3	Home dashboard	55
Figure 4	Journal and mood entry	56
Figure 5	Habit tracker and Life Balance Wheel	56
Figure 6	Progress analytics and calendar	57
Figure 7	Risk-screened AI reflection panel	57
Figure 8	Emergency grounding overlay	58

ABBREVIATION

Abbreviation	Full Form
AI	Artificial Intelligence
ML	Machine Learning
NLP	Natural Language Processing
API	Application Programming Interface
SPA	Single-Page Application
HTML	HyperText Markup Language
CSS	Cascading Style Sheets
JS	JavaScript
JSON	JavaScript Object Notation
DOM	Document Object Model
UI	User Interface
SVG	Scalable Vector Graphics
TTS	Text-to-Speech
CBT	Cognitive Behavioural Therapy
SCT	Social Cognitive Theory
TMSC	Transactional Model of Stress and Coping
HTTPS	Hypertext Transfer Protocol Secure
IDE	Integrated Development Environment

CHAPTER 1. INTRODUCTION

1.1 OVERVIEW OF THE PROJECT

Introduction

Stress, anxiety and low mood are widespread. Cost, limited availability of professionals and the stigma attached to seeking help keep many people from support. Technology-based self-help tools have grown quickly as a low-barrier complement to traditional services. Existing applications, however, usually address only one aspect of well-being: a journaling app records thoughts, a tracker records moods, a meditation app guides breathing, and a chatbot offers conversation. A person who wants all of these must move between several platforms.

MindScape addresses this by providing a single AI-assisted platform in which a user can record emotions, track moods and habits, reflect on thought patterns, practise grounding, review progress and, if they choose, request a gentle AI-generated reflection, all while keeping personal data on their own device.

Problem Statement

Existing digital well-being applications offer useful features such as journaling, mood tracking, meditation and conversational assistance, but they are scattered across separate apps. Conventional journaling tools also offer limited structured self-reflection, visualization and personalized feedback. The problem addressed in this project is:

How can a single AI-assisted platform unify emotional journaling, habit management and safety-aware reflection without fragmenting the user's well-being journey?

Objectives of the Project

- To design a single web platform that integrates journaling, mood tracking, habit and focus management, grounding activities and progress analytics.
- To provide structured self-understanding tools (such as thought-pattern and solution exploration) that go beyond free-form journaling.
- To provide opt-in AI-assisted reflection that is separate from the user's own entries and is preceded by a local risk-screening step.
- To keep personal data under the user's control through browser-local storage and JSON export/import.
- To support voice journaling and multilingual audio playback using native browser APIs.
- To visualize progress through charts, a calendar, achievements and a Life Balance Wheel.

System Overview

MindScape groups its functions into eight capability areas: Emotional Journal, Mood Tracking, Self-Understanding, Habit & Focus, Gratitude & Grounding, Progress Analytics, Achievements & Library, and Safe AI Reflection. The application is a client-side single-page application. All user data is held in the browser; the only network request is the on-demand call to the AI reflection API, and only after the local risk screening has passed.

Advantages of the System

- Unified experience: one platform instead of several separate apps.
- Privacy by default: data stays in the browser unless the user exports it.
- Safety-aware AI: crisis-indicating language is detected locally and the AI call is skipped.
- Low barrier: no account, installation or server is needed for the current prototype.
- Non-clinical framing: the platform supports reflection and does not diagnose or treat.

Applications

- Personal daily journaling and emotional self-reflection.
- Students managing stress, habits and focus.
- Habit-building and life-balance review through weekly and calendar views.
- Guided grounding and breathing during moments of stress.

1.2 SCOPE AND OBJECTIVE

Purpose of the Study

The purpose of this project is to design, implement and functionally validate an integrated, privacy-first digital well-being platform that combines self-tracking, reflection and AI-assisted guidance, while applying consistent safety and ethical constraints across every module.

General Objective

To build a usable, browser-based well-being platform that lets a person understand their emotional patterns and daily habits in one place and offers optional, risk-screened AI reflection without making any clinical claim.

Specific Objectives

- To implement the 18 functional modules of MindScape, organised into six user-facing groups.
- To implement local persistence using localStorage with JSON export and import.
- To implement a local risk-screening step that runs before any AI request and routes to a static grounding overlay when needed.

- To constrain the AI response to a fixed structured format so it can be shown in a clearly labelled, separate panel.
- To implement voice input and multilingual voice output with the Web Speech and SpeechSynthesis APIs.
- To verify the prototype through structured functional and structural testing.

Scope of the Project

Functional scope: journaling, mood and habit tracking, self-understanding tools, grounding and breathing activities, analytics, calendar, vision board, achievements, resource and wisdom libraries, and AI reflection with risk screening.

Technical scope: HTML5, CSS3 and JavaScript (ES6+) front end; browser localStorage; Canvas/SVG for visualization; Web Speech API and SpeechSynthesis API; one external generative AI API.

Out of scope: clinical diagnosis, treatment, clinical risk scoring, user accounts, a backend database and cross-device synchronization in the current prototype. No human-subjects evaluation of psychological effects has been carried out.

Importance of the Project

Combining several self-care functions in one privacy-respecting platform lowers the effort needed to build a reflective habit. Offering AI reflection as an optional, clearly separated feature, with a safety check in front of it, shows how generative AI can be added to a well-being tool responsibly.

Methodology for Achieving Objectives

1. Requirement analysis and literature review.
2. Module identification and interface design.
3. Implementation of the client-side application and local persistence.
4. Integration of the AI reflection pipeline with risk screening.
5. Integration of voice input and multilingual audio output.
6. Functional and structural testing.
7. Documentation and reporting.

Challenges and Limitations

- All data is scoped to a single browser; there is no cross-device synchronization.
- Voice quality and language support depend on the speech engines available on the user's device and browser.
- The AI reflection requires an internet connection.
- Keyword-based local risk screening cannot catch every expression of distress.

CHAPTER 2. LITERATURE REVIEW

2.1 LITERATURE OVERVIEW

The literature relevant to MindScape falls into three groups: (i) evidence on AI-guided reflective interventions and automated conversational agents, (ii) theoretical grounding for why guided reflection helps, and (iii) work on stigma as a barrier to seeking help, together with recent platforms that combine journaling, mood tracking and habit support.

AI-Guided Conversational and Reflective Interventions

Early automated conversational agents showed that structured dialogue delivered without a human can improve well-being. Fitzpatrick et al. evaluated the CBT-based chatbot Woebot in a randomized trial with young adults [2], and Ly et al. reported a pilot randomized trial of a fully automated agent for promoting well-being [3]. More recently, Wang et al. compared journaling, human-guided therapy and AI-guided therapy in a three-group experiment [1]. Both guided conditions improved emotional clarity more than journaling, and the AI-guided condition produced a distinctive reduction in perceived stigma. This finding motivates MindScape's decision to offer AI-guided reflection as an optional complement to private journaling.

Theoretical Grounding

Social Cognitive Theory [6] explains the benefit of guided interventions through observational learning: a model, human or AI, demonstrates how to identify and reframe emotions, and the user internalizes the pattern. The Transactional Model of Stress and Coping [7] treats emotional clarity as part of primary appraisal (judging what a stressor means) and stigma reduction as part of secondary appraisal (judging the resources available to cope). MindScape uses this reasoning conceptually to justify an optional AI-guided reflection alongside plain journaling.

Stigma as a Barrier to Help-Seeking

Stigma is a well-established deterrent to seeking help [1], [8]. Anonymous, non-judgmental digital formats are associated with lower perceived stigma than disclosure in person, which supports offering a private, low-stakes entry point for reflection.

2.2 LITERATURE SURVEY

Table 1 summarises the research papers reviewed for the project, with the contribution of each to the MindScape design.

Table 1: Literature survey

No.	Research Paper	Year	Key Contribution
1	AI-driven mental health therapy: a comparative study of emotional clarity and stigma reduction	2026	Compares journaling, human therapy and AI-guided reflection

No.	Research Paper	Year	Key Contribution
2	ZenLoop: An AI-Powered Mental Health Platform	2025	AI conversational support with mood tracking and self-help tools
3	AI-Based Mental Health Chatbot with Journaling, Mood Tracking and Emergency SOS	2026	Emergency crisis detection alongside mood and journaling
4	The Personal Mental Wellbeing Assistant (Mood, Journal, Habits, Recommendations)	2025	Combines habit management with journaling and mood tracking
5	AI Mood Tracking Application	2025	ML models tracking long-term mood fluctuations
6	Emotional Journal with Mood Tracking	2025	NLP analysis of text-based mood and journal entries

Research Gap

The surveyed tools tend to cover one or two functions, such as chatbot plus mood tracking, or journaling plus NLP analysis. Few combine journaling, mood tracking, habit and focus management, grounding, analytics and safety-aware AI reflection in a single local-first platform. Table 2 contrasts MindScape with the categories of prior tools.

Table 2: Comparison of MindScape with prior tools

Aspect	Prior Tools	MindScape
Guidance	Journaling apps: none. Chatbots: clinically framed	Opt-in, non-clinical AI reflection
Diagnostic framing	Often implicit or explicit (for example, CBT “therapy”)	Explicitly avoided; self-report only
Data model	Typically cloud-account based	Local-first; user-controlled export
Cultural content	Rarely addressed	Multi-tradition, opt-in only
Crisis handling	Varies; often AI-dependent	Static, always available, AI-independent

CHAPTER 3. SYSTEM DESIGN

3.1 EXISTING SYSTEM

Existing solutions are either (a) private journaling and mood-tracking applications that give no structured, model-driven feedback, or (b) AI conversational agents framed as therapy, which can imply clinical authority that a consumer product has not earned. Features such as habit tracking, grounding exercises and analytics are usually found in separate applications, so users must switch between platforms and their data is split across them. Many tools also depend on cloud accounts, which raises privacy concerns for sensitive emotional content.

3.2 PROPOSED SYSTEM

MindScape is a single, local-first web platform that integrates the functions above and adds optional AI reflection. Four principles govern the design:

1. Local-first data ownership, to minimise privacy exposure.
2. Non-diagnostic, transparent self-report scoring, to avoid implied clinical authority.
3. Opt-in, user-selected cultural and wisdom content that is never auto-assigned.
4. A crisis-support pathway that works independently of the AI module and the network.

3.3 SYSTEM ARCHITECTURE

The prototype is a client-only single-page application. Figure 1 shows the flow of data through the system, from user interaction to visualization and AI reflection.




Figure 1: MindScape data-flow architecture

Table 3: Architectural layers of MindScape

Layer	Technology
Presentation	HTML5, CSS3 (Grid, Flexbox, custom properties)
Application logic	Vanilla JavaScript (ES6+), no external UI framework
Browser Web APIs	Web Speech API, SpeechSynthesis API, Canvas API, FileReader API
Persistence	Client-side localStorage; JSON export / import
External call	HTTPS request to a generative AI language model API (on demand only)

The only class of network request in the prototype is a risk-filtered text payload sent to the AI API when the user explicitly requests a reflection. No user account, server or database is needed to run the prototype.

Functional Module Groups

The 18 functional modules are organised into six user-facing groups, as listed in Table 4.

Table 4: Functional module groups

Group	Representative Modules
Self Reflection	Dream/scenario journal, gratitude journal, search and bookmarks
Self-Understanding	Vulnerability index, solution explorer, thought patterns
Productivity	Focus timer, habit tracker, vision board, life balance wheel
Healing	Guided breathing, affirmations, emergency grounding overlay
Insights	Progress analytics, weekly review, calendar, achievements
Wisdom & AI	Perspective-shift drawer, multilingual audio, AI reflection

3.4 HARDWARE REQUIREMENTS

Table 5: Hardware requirements

Component	Requirement
Processor	Intel Core i3 (recommended: i5)
RAM	4 GB (recommended: 8 GB or more)
Storage	10 GB free space
Internet	Required for AI API interaction

3.5 SOFTWARE REQUIREMENTS

Table 6: Software requirements

Component	Requirement
Operating system	Windows / Linux / macOS
IDE	Visual Studio Code
Frontend	HTML5, CSS3, JavaScript

CHAPTER 4. IMPLEMENTATION

4.1 METHODOLOGY

MindScape was developed incrementally. Core data handling (journal entries, moods, habits, tasks and gratitude records) was built first on top of localStorage. Visualization and analytics modules were then layered on the stored data, followed by the grounding and healing modules, the AI reflection pipeline with its risk screening, and finally voice input and multilingual audio. The project followed the review schedule of the department: Review 0 (abstract with base paper), Review 1 (problem analysis and planning), Review 2 (design and implementation), Review 3 (testing and final results) and the final report submission.

The data flow of the application has six stages:

1. User interaction: journal entries, moods, habits, tasks and gratitude records are entered.
2. Data acquisition: inputs are converted to structured data objects.
3. Data persistence: objects are stored locally via browser localStorage.
4. Data processing: JavaScript computes mood statistics, streaks and progress.
5. Visualization: charts, calendars, badges and the Life Balance Wheel are drawn.
6. AI reflection: a risk-screened prompt is sent to the AI reflection API on request.

4.2 IMPLEMENTATION

4.2.1 Journal and Mood Module

Users record dreams, thoughts, scenarios and moods with categories. Entries are saved as structured objects in localStorage and survive page reloads. A search and bookmark function lets users find and mark entries, and mood values feed the statistics and calendar views.

4.2.2 Self-Understanding Module

This module provides a self-report vulnerability index, a solution explorer and a thought-pattern tool. The vulnerability index is user-entered, shown transparently through a gauge that updates with slider input, and labelled as non-clinical. It is not a diagnostic score.

4.2.3 Productivity Module

A focus timer, habit tracker, task list, vision board and Life Balance Wheel help the user plan and review daily life. Streaks and completion statistics are calculated in JavaScript from stored records, and the Life Balance Wheel is drawn with Canvas/SVG.

4.2.4 Gratitude and Grounding Module

Gratitude journaling, guided breathing and affirmations support everyday healing activities. An emergency grounding overlay is always available and does not depend on the AI module or the network.

4.2.5 Analytics and Achievements Module

Progress analytics, a weekly review and a calendar visualization show emotional and habit patterns over time. Achievement badges are unlocked by usage consistency, such as check-in frequency, rather than by a claimed emotional outcome, so that a difficult day is never presented as a failure.

4.2.6 Risk Screening and AI Reflection Module

A request can start from a saved journal entry or from a selected problem tag such as “exam fear” or “workplace conflict”. Figure 2 shows the pipeline.




Figure 2: Risk-screened AI reflection pipeline

1. Risk screening: the text is checked locally against crisis-indicating patterns before any network call.
2. Prompt assembly: a system prompt is built from the user’s opted-in wisdom traditions and chosen output language.
3. Generation: a structured request is sent to the AI language model API.
4. Rendering: the structured reply is shown in a clearly labelled panel, separate from the user’s own entries.

If risk-indicating language is detected, the API call is skipped and the static grounding overlay with support resources opens instead. The model is constrained to return a fixed JSON structure

with an emotion summary, a short original story (80–120 words), a paraphrased quote (under 20 words), a lesson, a practical step and a reflection question. The module never uses the words “therapy” or “therapist”, never produces a risk or severity score, and never assigns a wisdom tradition automatically.

4.2.7 Voice and Multilingual Module

The Web Speech API provides voice journaling, and the SpeechSynthesis API reads reflections aloud in the selected language. Quality depends on the speech engines available on the user’s device and browser.

4.2.8 Data Management Module

Settings let the user export all data to a JSON file and import it again. This restores the application state after browser storage has been cleared and gives the user full control over their data.

4.3 SAFETY AND ETHICAL DESIGN

Five constraints are applied consistently across every module:

- Non-diagnostic scoring: reflective indices are transparent, user-entered and labelled as non-clinical.
- Privacy by default: no data leaves the device except the text sent for AI reflection, and only on explicit request.
- AI-independent crisis handling: the grounding pathway and helpline information work without AI or network access.
- Cultural sensitivity: wisdom content from any tradition is opt-in only and never inferred.
- Engagement-based rewards: badges reflect consistency, not emotional outcomes.

CHAPTER 5. CONCLUSION AND FUTURE WORK

5.1 CONCLUSION

MindScape demonstrates that journaling, mood tracking, habit management, grounding, analytics and optional AI reflection can be unified in one privacy-first web platform. The risk-screened AI pipeline, the AI-independent crisis pathway and the consistent non-clinical framing show how generative AI can be added to a well-being tool responsibly. Functional and structural testing confirm that the prototype works as designed across its modules. The central open question, whether the AI reflection module delivers measurable benefits in emotional clarity, coping and stigma reduction, requires a controlled study with users, which is proposed as future work.

5.2 FUTURE WORK

- A server-side proxy for AI API calls so that credentials never reach the client.
- User accounts and cross-device synchronization.
- A controlled between-subjects evaluation comparing AI-guided reflection with plain journaling, using validated emotional-clarity and perceived-stigma scales.
- An opt-in, k-anonymity-protected aggregate view of group mood trends for consenting groups such as a class or team.
- An on-screen AI companion with voice and expressive interaction, supported in all five languages (English, Tamil, Malayalam, Telugu and Hindi).
- Wider multilingual support and improved voice quality.

5.3 SOURCE CODE

The main source files of the MindScape prototype are listed below, in the order in which they are loaded and used.

```
<!DOCTYPE html>
<html lang="en">
<head>
    <meta charset="UTF-8">
    <meta name="viewport" content="width=device-width, initial-scale=1.0">
    <title>MindScape - Mental Wellness</title>

    <style>
        body {
            font-family: Arial, sans-serif;
            background: #f4f0ff;
            text-align: center;
            margin: 0;
            padding: 20px;
            color: #333;
        }

        h1 { color: #7254b5; }

        section {
            background: white;
            padding: 20px;
            margin: 20px auto;
            max-width: 500px;
            border-radius: 12px;
            box-shadow: 0 3px 10px #ddd;
        }

        button {
            background: #7254b5;
            color: white;
            border: none;
            padding: 10px 16px;
            margin: 5px;
            border-radius: 6px;
            cursor: pointer;
        }

        textarea {
            width: 90%;
            height: 100px;
            padding: 10px;
            border: 1px solid #ccc;
            border-radius: 6px;
        }

        #breath {
            font-size: 22px;
            color: #7254b5;
            margin: 25px;
        }
    </style>
</head>

<body>
```

```
    <h1>MindScape</h1>
    <p>Your Personal Mental Wellness Companion</p>

    <nav>
        <button onclick="openPage('dashboard')">Dashboard</button>
        <button onclick="openPage('journal')">Journal</button>
        <button onclick="openPage('grounding')">Grounding</button>
    </nav>

    <section id="dashboard">
        <h2>Welcome to MindScape</h2>
        <p>Take a moment for yourself. Your well-being matters.</p>
    </section>

    <section id="journal" hidden>
        <h2>Daily Journal</h2>
        <textarea id="note" placeholder="Write your thoughts
here..."></textarea>
        <br>
        <button onclick="saveNote()">Save Journal</button>
        <p id="message"></p>
        <h3>Previous Entries</h3>
        <div id="entries"></div>
    </section>

    <section id="grounding" hidden>
        <h2>Breathing Exercise</h2>
        <p>Follow the prompts and breathe gently.</p>
        <p id="breath">Ready to relax?</p>
        <button onclick="startBreathing()">Start</button>
        <button onclick="stopBreathing()">Stop</button>
    </section>

    <script>
        // APP NAVIGATION
        function openPage(page) {
            document.querySelectorAll("body > section").forEach(s => {
                s.hidden = s.id !== page;
            });

            if (page === "journal") showEntries();
        }

        // STORAGE
        const Storage = {
            save(key, data) {
                let items = this.get(key);
                items.push(data);
                localStorage.setItem(key, JSON.stringify(items));
            },

            get(key) {
                return JSON.parse(localStorage.getItem(key) || "[]");
            }
        };

        // JOURNAL
        function saveNote() {
            const note = document.getElementById("note").value.trim();

            if (!note) {
                document.getElementById("message").textContent =
```

```
                    "Please write something first.";
                return;
            }

            Storage.save("mindscape_journal", {
                note: note,
                date: new Date().toLocaleString()
            });

            document.getElementById("note").value = "";
            document.getElementById("message").textContent = "Journal
saved!";
            showEntries();
        }

        function showEntries() {
            const entries = Storage.get("mindscape_journal");
            document.getElementById("entries").innerHTML = "";

            entries.slice().reverse().forEach(entry => {
                const item = document.createElement("p");
                item.textContent = entry.date + " — " + entry.note;
                document.getElementById("entries").appendChild(item);
            });
        }

        // BREATHING EXERCISE
        const steps = [
            "Breathe in gently",
            "Hold comfortably",
            "Breathe out slowly"
        ];

        let timer = null;
        let step = 0;

        function startBreathing() {
            stopBreathing();
            step = 0;

            document.getElementById("breath").textContent = steps[step];

            timer = setInterval(() => {
                step = (step + 1) % steps.length;
                document.getElementById("breath").textContent = steps[step];
            }, 4000);
        }

        function stopBreathing() {
            if (timer !== null) {
                clearInterval(timer);
                timer = null;
            }

            document.getElementById("breath").textContent = "Take your time
and relax.";
        }

        // SHOW DASHBOARD AT START
        openPage("dashboard");
    </script>

</body></html>
```

5.3 RESULTS

The prototype was validated through structured manual functional testing across all 18 modules, together with automated structural checks: HTML tag-balance verification, JavaScript syntax validation, and a cross-check that every DOM element referenced in the application logic exists in the markup. Table 7 lists representative test cases.

Table 7: Representative functional test cases

ID	Module	Result
TC-01	Journal	Entry persists correctly across a full page reload
TC-02	Risk screening	Crisis-indicating text opens the grounding overlay; API call is skipped
TC-03	AI Reflection	Structured output is rendered separately from journal entries
TC-04	Vulnerability Index	Gauge and score update transparently with slider input
TC-05	Settings	Full data export/import restores state after storage was cleared

This validation is functional and structural only. No human-subjects evaluation of the psychological effects of MindScape has been conducted.

Output Screens




Figure 3: Home dashboard




Figure 4: Journal and mood entry




Figure 5: Habit tracker and Life Balance wheel




Figure 6: Progress analytics and calendar

REFERENCES

[1] R. Wang, K. L. Siau, and Z. Zhang, “AI-driven mental health therapy: A comparative study of emotional clarity and stigma reduction across journaling, human-guided therapy, and AI-guided therapy,” Decision Support Systems, vol. 207, p. 114696, 2026.

[2] K. K. Fitzpatrick, A. Darcy, and M. Vierhile, “Delivering cognitive behavior therapy to young adults with symptoms of depression and anxiety using a fully automated conversational agent (Woebot): A randomized controlled trial,” JMIR Mental Health, vol. 4, no. 2, e7785, 2017.

[3] K. H. Ly, A.-M. Ly, and G. Andersson, “A fully automated conversational agent for promoting mental well-being: A pilot RCT using mixed methods,” Internet Interventions, vol. 10, pp. 39–46, 2017.

[4] A. T. Beck, Cognitive Therapy and the Emotional Disorders. London, U.K.: Penguin, 1979.

[5] World Health Organization, World Mental Health Report: Transforming Mental Health for All. Geneva, Switzerland: WHO, 2022.

[6] A. Bandura, Social Foundations of Thought and Action. Englewood Cliffs, NJ, USA: Prentice-Hall, 1986.

[7] R. S. Lazarus and S. Folkman, Stress, Appraisal, and Coping. New York, NY, USA: Springer, 1984.

[8] S. Clement et al., “What is the impact of mental health-related stigma on help-seeking? A systematic review of quantitative and qualitative studies,” Psychological Medicine, vol. 45, no. 1, pp. 11–27, 2015.